

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-007-23756-01-00
 Spot: S2S2SESE Sec/Twnshp/Rge: 13-35S-11W
205 feet from S Section Line, 680 feet from E Section Line
 Lease Name: ROBERT Well #: 1-13H
 County: BARBER Total Vertical Depth: 4866 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4870		WITH 50 SX CMT
I1	7	5397	2246	
L1	4.5	11082		WITH 630 SX CMT
SURF	9.625	955		WITH 245 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/06/2015 8:10 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Rcvd. from: STEVE JOHNSON Company: SANDRIDGE EXPLORATION Phone: (405) 429-5000

Proposed Plugging Method: CIBP @ 4870' WITH 50 SX CMT. PLUG AT 1000' WITH 100 SX CMT. PLUG AT 500' WITH 60 SX CMT. PLUG AT 0-40' WITH 25-30 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 08/06/2015 10:00 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4870' WITH 50 SX CMT. 1ST PLUG AT 1002.59' WITH 50 SX CMT. 2ND PLUG AT 502.47' WITH 60 SX CMT. TOP OFF FROM 66.10' WITH 25 SX CMT.

MTD = 9,999 (ACO-1)

Perfs:

Top	Bot	Thru	Comments
8953	8955		
8818	8820		
8683	8685		
8548	8550		
8270	8280		
8134	8145		
8008	8010		
7873	7875		
7738	7740		
7603	7605		
7468	7470		
7333	7335		
7198	7200		
7063	7065		
6928	6930		
6793	6795		
6658	6660		
6523	6525		
6388	9999		
6253	6255		
6118	6120		
5983	5985		
5844	5850		
5713	5715		
5578	5580		
5443	5445		
5308	5310		
5173	5175		
5038	5040		
843	8415		

KCC WICHITA
 8-10-2015
 AUG 10 2015
 RECEIVED

8/19/15 cmv

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

Form CP-2/3

RECEIVED
AUG - 7 2015 *MP*
KCC DODGE CITY

KCC WICHITA
AUG 10 2015
RECEIVED