

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-21621-00-01  
Spot: S2N2NE Sec/Twnshp/Rge: 1-34S-5W  
990 feet from N Section Line, 1320 feet from E Section Line  
Lease Name: LANA Well #: 1-A  
County: HARPER Total Vertical Depth: 4742 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4737	3001	160 SX
SURF	8.625	260		200 SX
T1	2.375	4284		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/28/2015 12:00 AM

Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.

Proposal Rcvd. from: RON ORR Company: ORR ENTERPRISES, INC. Phone: \_\_\_\_\_

Proposed Plugging Method: CIBP @ 4281' & 10 SXS. LOAD HOLE WITH MUD. REC & LAY DOWN CASING. SPOT 60 SXS @ 904', 60 SX @ 610' AND CIRCUALTE @ 312'-0'.

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: PARTIAL

Date/Time Plugging Completed: 07/30/2015 6:30 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @ 4281' & 10 SXS CEMENT. LOAD HOLE WITH MUD. RECOVERED CASING FROM 3001'. RAN TUBING TO 904' SPOTTED 60 SXS CEMENT. PULLED TUBING TO 610' SPOTTED 60 SXS.. PULLED TUBING TO 312' & CIRCUALTED CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4596	4604	CSG	
4331	4604	CSG	

Remarks: ORR ENTERPRISES -- CLASS C CEMENT

Plugged through: TBG

District: 02

Received \_\_\_\_\_ Signed \_\_\_\_\_  
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

AUG 12 2015

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*JK*

*[Signature]*  
8/19/15 *OKM*