

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-19370-00-00  
Spot: NESWSWSW Sec/Twnshp/Rge: 1-29S-14E  
568 feet from S Section Line, 355 feet from W Section Line  
Lease Name: HOWARD Well #: H-1  
County: WILSON Total Vertical Depth: 1140 feet

Operator License No.: 34697  
Op Name: WILSON COUNTY HOLDINGS LLC  
Address: 1135 N. 15TH ST.  
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1140		145 SX
SURF	6.625	50		7 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/30/2015 2:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Pull production tubing from well. Run cement string and wash well to TD. Pump cement from bottom to top. Pull cement string and top well off with cement. Dig well and cut off below plow depth, and bury.

KCC WICHITA  
AUG 13 2015  
RECEIVED

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 07/30/2015 2:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375 inch cement string was run to 1120 ft. The well was then pumped full of cement from btm to top using 1 sack of cottonseed hulls. A total of 143 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

RECEIVED  
KCC DIST # 3  
AUG 07 2015  
CHANUTE, KS

AD

Remarks:

Plugged through: TBG

8/19/15 ccm

District: 03

Signed

Alan Dunning  
(TECHNICIAN)