

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-20545-00-01
Spot: NESWNENE Sec/Twnshp/Rge: 12-29S-14E
4340 feet from S Section Line, 820 feet from E Section Line
Lease Name: BERCKEFELDT Well #: 5
County: WILSON Total Vertical Depth: 1152 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4	1137		122 SX
SURF	4	40		2 SX

Well Type: EOR UIC Docket No: E23934.1 Date/Time to Plug: 12/10/2012 10:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE Phone: (620) 433-7196

Proposed Plugging Method: Run cement string to TD and pump full.

KCC WICHITA
AUG 13 2015
RECEIVED

Plugging Proposal Received By: ALAN DUNNING WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2015 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The 2.375 inch tubing could not be removed and therefore was perforated at 500 ft and 1000 ft. A cement string was then lowered to 1120 ft and the well pumped full of cement. A total of 119 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KCC DIST #3
AUG 07 2015
CHANUTE, KS

AD

Remarks:

Plugged through: TBG

8/19/15 cm

District: 03

Signed Alan Dunning
(TECHNICIAN)