

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-21872-00-00
Spot: NW Sec/Twnshp/Rge: 12-29S-14E
2626 feet from N Section Line, 2563 feet from W Section Line
Lease Name: DEL REY INDUSTRIES Well #: 9
County: WILSON Total Vertical Depth: 332 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	332		42 SX
SURF	6.625	50		7 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2015 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Pull production tubing from well. Run tubing and wash well to TD. Pump cement from bottom to top. Pull cement string and top well off with cement. Dig well and cut off below plow depth, and bury.

KCC WICHITA
AUG 13 2015
RECEIVED
8-13-2015

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 07/20/2015 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The wellhead was hooked onto and then pumped full of cement by squeezing. The well was shut in with 500 psi. A total of 49 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

RECEIVED
KCC DIST # 3
AUG 07 2015
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

8/19/15 cpm

District: 03

Signed Alan Dunning
(TECHNICIAN)