

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-21908-00-00
Spot: NW Sec/Twnshp/Rge: 12-29S-14E
2626 feet from N Section Line, 2300 feet from W Section Line
Lease Name: DEL REY INDUSTRIES Well #: 10
County: WILSON Total Vertical Depth: 1145 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1135		200 SX
SURF	6.625	50		7 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2015 3:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Pull production tubing from well. Run tubing and wash well to TD. Pump cement from bottom to top. Pull cement string and top well off with cement. Dig wellhead and cut off below plow depth, and bury.

KCC WICHITA
AUG 13 2015
RECEIVED

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 07/20/2015 3:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The wellhead was hooked onto and the well pumped full of cement by squeezing. The well was then shut in with 600 psi. A total of 45 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

RECEIVED
KCC DIST #3
AUG 07 2015
CHANUTE, KS
AD

Remarks:

Plugged through: CSG

8/19/15 cam

District: 03

Signed Alan Dunning
(TECHNICIAN)