

1091062

TO: STATE CORPORATION COMMISSION

API NUMBER 15-057-20,409-0001  
C NW NW SEC. 27-2, T 27 S, R 21 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MOLITOR "A" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY FORD 159.77

OPERATOR LICENSE # 5118

WELL TOTAL DEPTH 4916 FEET

OPERATOR: TGT PETROLEUM CORPORATION PRODUCTION CSG: SIZE 5 1/2" @ 4920' WITH 395 SX

NAME AND 7570 W 21ST BLDG 1010 STE D SURFACE CASING: SIZE 8 5/8" @ 544' WITH      SX

ADDRESS WICHITA, KS 67205

ABANDONED OIL WELL  GAS WELL  INPUT WELL  INJ WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 12:30 PM DAY: 27 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM HAROLD BELLERIVE

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4485-88

1ST PLUG CIBP AT 4400' WITH 5 SX ON TOP. 2ND PLUG PULL TO 1360'. LOAD HOLE WITH MUD.

SPOT 50 SX CEMENT. 3RD PLUG PULL TO 570'. SPOT 50 SX CEMENT. 4TH PLUG PULL TO 40'.

SPOT 10 SX CEMENT. STAYED FULL.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  X NONE

OPERATIONS COMPLETED: HOUR: 2:40 PM DAY: 27 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

1ST PLUG CIBP AT 4400' WITH 5 SX ON TOP. 2ND PLUG PULL TO 1360'. LOAD HOLE WITH MUD.

SPOT 50 SX CEMENT. 3RD PLUG PULL TO 570'. SPOT 50 SX CEMENT. 4TH PLUG PULL TO 40'.

SPOT 10 SX CEMENT. STAYED FULL.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1400' OF 5 1/2" CASING  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

**INVOICED**

SIGNED [Signature]  
(TECHNICIAN)

DATE 7/5/00

WV. NO. 1060004

FORM CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION

JUL 03 2000  
7-3-2000

CONSERVATION DIVISION  
Wichita, Kansas

[Signature]