

2 060495

6-2-87

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 015-22,105-0000

NW NE SE, SEC. 26, T 29 S, R 6 WE
1950 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5437

Lease Name Blair East Well # 1

Operator: Tomco Oil Company

County Butler 78.29

Name & Address Box 1372

Well Total Depth 2409 PB1915 feet

Atlanta, KS

Conductor Pipe: Size 5 1/2 feet 2408

Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Perforated 1772-80

Plugging Contractor B & S Well Service License Number 6013

Address Box 837, Winfield, KS 67156

Company to plug at: Hour: Day: 26 Month: 5 Year: 19 87

Plugging proposal received from Dale Smith

(company name) B & S Well Service (phone)

were: Sand bottom to 1720' and dump six sacks cement. Shoot and pull pipe.

Build bridge from 300-275'. Bail dry and dump five yards redi-mix. Cut off pipe, plate and bury.

Plugging Proposal Received by Ron Wilson (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 Day: 2 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT Sanded bottom to 1720' and dumped six sacks cement. Shot and pulled 1000' of 5 1/2". Built bridge from 300-275' and bailed dry. Daniels Redi-mix dumped five yards of sand redi-mix cement to surface.

Remarks: Ticket #12252

RCD 6-9-87 JUN 9 1987

(If additional description is necessary, use BACK of this form.)

INVOICED (could not observe this plugging.)

Signed [Signature] (TECHNICIAN)

DATE 6-9-87 WK

INV. NO. 17191 6-2