

6-4-87

2 060496

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 015-22,301-0000
C SE, SEC. 26, T 29 S, R 6 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 5437
Operator: Tomco Oil Company
Name & Address: R.R. #1, Box 137A
Atlanta, KS

feet from S section line
feet from E section line
Lease Name Blair East Well # 2
County Butler County 94.28
Well Total Depth 2901 PB 2800 feet
Conductor Pipe: Size 5 1/2 feet 2900
Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well Gas Well Input Well SWD Well X D&A
Other well as hereinafter indicated Perforated from 1866-80

Plugging Contractor B & S Well Service License Number 6013
Address Box 837, Winfield, KS 67156

Company to plug at: Hour: Day: 2 Month: 6 Year: 19 87

Plugging proposal received from Dale Smith
(company name) B & S Well Service (phone)

were: Push plug to 1900' and sand to 1800' and dump six sacks cement. Shoot and pull pipe. Build bridge from 300-275' and bail dry, then dump full of redi-mix.

Plugging Proposal Received by Ron Wilson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None
Operations Completed: Hour: 12:00 Day: 4 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT Pushed plug approximately 1900' and graveled to 1800'. Dumped six sacks cement. Shot and pulled 5 1/2" casing. Built bridge from 300-275'. Bailed dry and dumped five yards redi-mix.

6-9-87 JUN 9 1987

Remarks: Daniels#12314 (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-9-87 WK

INV. NO. 17192 6-4

Signed Ron Wilson (TECHNICIAN)