

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-00080-00-01  
Spot: NENENE Sec/Twnshp/Rge: 25-27S-13W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: ROLNGSN-SIMP Well Number: 2  
County: PRATT Total Vertical Depth: 4463 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: P.O. BOX 20380  
WICHITA, KS 67208

Production Casing Size: 2.875 feet: 4398 WITH 75 SX CMT  
Surface Casing Size: 10.75 feet: 324

*# 145<sup>05</sup>*

Well Type: EOR UIC Docket No: E13954.1 Date/Time to Plug: 10/23/2003 9:30 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: JASON BRUNS Company: BEREN CORPORATION Phone: (316) 265-3311

Proposed Plugging Method: PUMP 200# HULLS & 10 SX GEL. PLUG AT 800' WITH 50 SX CMT. PLUG AT 350' WITH 70 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/23/2003 1:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PBTD 4310'. PERFS AT 4360-75. CIBP @ 4310'. PERFS AT 3800-06'. 5 1/2" IN PLACE AT 3110-4459'. PUMP DOWN 2 7/8" CASING WITH 20 SX CMT. PUMPED 50# HULLS AHEAD OF CMT & 50# HULLS IN WITH CMT. SPOT PLUGS THROUGH 2 7/8" CASING. 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT WITH 50# HULLS MIXED IN. 2ND PLUG AT 350' WITH 70 SX CMT WITH 50# HULLS MIXED IN. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED  
OCT 31 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY UNITED CEMENTING. RECOVERED 1311' OF 2 7/8" CASING.

Plugged through: CSG

District: 01



Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

INVOICED  
DATE 10-31-03  
TEL NO. 2004060713

*[Signature]*  
Form CP-2/3