

TQ:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-00126-00-00
Spot: CNENENW Sec/Twnshp/Rge: 13-27S-13W
330 feet from N Section Line, 2310 feet from W Section Line
Lease/Unit Name: LUDEA A Well Number: 1
County: PRATT Total Vertical Depth: 4412 feet

Operator License No.: 5097
Op Name: MARTIN OIL PRODUCERS, INC.
Address: 150 N. MAIN, STE 1010
WICHITA, KS 67202

Conductor Pipe: Size feet: 8143-39
Surface Casing: Size 8.625 feet: 353 WITH 250 SX CMT
Production: Size 5.5 feet: 4412 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/12/2002 3:45 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: TRACY BLACK Company: MARTIN OIL Phone: (620) 523-9034

Proposed Plugging Method: SAND TO 4240' & 5 SX CMT. PLUG AT 750' WITH 10 SX GEL - 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT OR PERFORATE AT 750' & CIRCULATE TO SURFACE WITH 300 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/13/2002 10:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PBTD 4376'. PERFS AT 4310-15, 4301-04, 4292-4301'. ONLY HAD 2" OF STRETCH IN 5 1/2" CASING. SUSPECT 5 1/2" CASING WAS SQUEEZED IN. SANDED BACK TO 4200' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PERFORATED 5 1/2" CASING AT 750'. TOOK INJECTION RATE AT 1 1/2 BPM AT 600#. (PUMPED CAPACITY OF 5 1/2" CASING TO 750' & 50 SX CMT) PUMP DOWN 5 1/2" CASING WITH 110 SX CMT. MAXIMUM PRESSURE 650#. SHUT IN PRESSURE 0#. 5 1/2" CASING WENT ON VACUUM. PUMPED DOWN 5 1/2"/8 5/8" ANNULUS WITH 125 SX CMT. MAXIMUM PRESSURE 100#. SHUT IN PRESSURE 25#. 12/13/02: CHECK CMT TOPS. 5 1/2" CASING TOP AT 390'. 5 1/2"/8 5/8" ANNULUS AT 90'. TOPPED OUT 5 1/2"/8 5/8" ANNULUS WITH 25 SX CMT. RUN 2 7/8" TUBING IN TO 350'. CIRCULATED 5 1/2" CASING FROM 350' TO SURFACE WITH 35 SX CMT. PULLED TUBING OUT & TOPPED OFF 5 1/2" CASING & 5 1/2"/8 5/8" ANNULUS WITH 5 SX CMT.

RECEIVED
12-20-2002
DEC 20 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 12-23-02
INV. NO. 2003060974

[Handwritten signature]