

To: 1 040723
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-11

API NUMBER 15-151-10321-0000 81 P

NE NE NE, SEC. 13, T. 27 S, R. 13 W&E

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30481

Lease Name Luders Well # 1

Operator: Apollo Energies, Inc.

County Pratt

Name & Address RR 1, Box 60

Well Total Depth 4340 141.05 feet

Kingman, KS 67068

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 480

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address 112 W. Fowler, Medicine Lodge, KS

Company to plug at: Hour: 2 p.m. Day: 11 Month: 12 Year: 19 92

Plugging proposal received from Jim Byers

(company name) Apollo Energies, Inc. (phone) 316-532-2390

work: 5 1/2" at 4340' w/110 sx cement, PBSD 4325', Perfs at 4295-4300', 4240-49', 4212-26'
1st plug sand back to 4150' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 100 sx cement,

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 11 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4150' and dumped 5 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls and 100 sx cement,

Maximum pressure 150 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1850' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form)

(old / ~~xxxxxxx~~) observe this plugging.

DATE 1-11-93

INV. NO. 37174

12-11-92 FEB 24 1993

Signed Stephen J. Pfeiffer
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
12-15-92
15 1992
CONSERVATION DIVISION
WICHITA, KANSAS