

To: 1 040589  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5097

Operator: Martin Oil Producers, Inc.  
Name & Address  
150 N. Main  
Wichita, KS 67202

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pullers License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 12 Month: 11 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pullers (phone) 316-938-2943

were: 5 1/2" at 4343' w/125 sx cement, PBTD 4332', Perfs at 4200-4204, 4178-86'

Casing parted (pulled out of cellar-pin split) at 458' when working casing.

1st plug sand back to 4128' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 10 sx gel and 175 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11 a.m. Day: 12 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4128' and dumped 5 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 10 sx gel and 175 sx cement.

Maximum pressure 50 psi and shut in 50 psi.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 19 1991

11-19-91  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 458' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

**INVOICED**

DATE 12-4-91  
33928

Signed Stephen J. Durrant  
(TECHNICIAN)