

To: 1 040722 12-11  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-10322-0000 -802  
NE SE NE, SEC. 13, T 27 S, R 13 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 30481

3630 feet from S section line  
330 feet from E section line

Operator: Apollo Energies, Inc.  
Name:  
Address: RR 1, Box 60  
Kingman, KS 67068

Lease Name Luders Well # 2  
County Pratt

Well Total Depth 4339 141.02 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 468

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address 112 W. Fowler, Medicine Lodge, KS

Company to plug at: Hour: 5:15 p.m. Day: 11 Month: 12 Year: 19 92

Plugging proposal received from Jim Byers

(company name) Apollo Energies, Inc. (phone) 316-532-2390

work: 5 1/2" at 4339' w/110 sx cement. PBTD 4330', Perfs at 4277-4325'

1st plug sand back to 4100' and dump-5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper

plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6 p.m. Day: 11 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4207' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 100 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied.. Recovered 2160' of 5 1/2" casing.

RECEIVED STATE CORPORATION COMMISSION

INVOICED

(If additional description is necessary, use BACK of this form)

I (did) ~~not~~ observe this plugging.

DATE 1-11-93

Signed [Signature] (TECHNICIAN)

INV. NO. 37175 FEB 24 1993