

1 080541

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-20,124-0000
NW SW SE SEC. 2, T 27 S, R 13 W/E
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

Lease Name Sheegog Well # 2

Operator: Bowers Drilling Company, Inc.
Name & Address 125 N. Market, Ste. 1425
Wichita, KS 67202

County Pratt 144.30
Well Total Depth 4440 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 425

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Bowers Drilling Company, Inc. License Number 5435

Address 125 N. Market, Ste. 1425, Wichita, KS 67202

Company to plug at: Hour: 8:30 am Day: 1 Month: August Year: 19 86

Plugging proposal received from Bill Musgrove

(company name) Bowers Drilling Company, Inc. (phone) (316) 886-5520

were: 5 1/2" (14#) at 4439' PBSD at 3972' Perfs at 3826-3940' Anhydrite 775'

1st plug sand back to 3700' and dump 4 sx cement on top of sand through bailer

2nd plug at 775' with 35 sx cement through tubing

3rd plug at 425' with 25 sx cement through tubing

4th plug at 40-0' with 10 sx cement through tubing

5th plug pump or spot with 1" tubing to fill backside allow up to 100 sx cement.

Squeezed at 750' Plugging Proposal Received by Don C. Ubel
5 1/2" casing (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:45 am Day: 1 Month: August Year: 1986

ACTUAL PLUGGING REPORT 1st plug spotted 30 sx cement through 2" tubing at 775', pulled

tubing up to 425'; 2nd plug spotted 25 sx cement through tubing, pulled tubing up

to 60'; 3rd plug spotted 10 sx cement to surface; 3rd plug pumped 100 sx cement down

backside.

* Bottom plug sanded back to 3700' and dumped 4 sx cement on top of sand through
bailer.
Maximum pressure 175 psi and shut in 50 psi.

Remarks: No casing was recovered. Squeezed at 750'. Used Halco light cement by Halliburton.
Additional description is necessary, use BACK of this form.

INVOICED

DATE 8-7-86
INV. NO. 14673
P-1

Signed J. A. [Signature] AUG 7 1986
(TECHNICIAN)

REC 8-7-86