

10-29-87 15-151-20135-0000

To: 1 120038  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA  
E/2 E/2 SW, SEC. 2, T 27 S, R 13 W/E  
1320 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5435  
Operator: Bowers Drilling Inc.  
Name & Address: 125 N. Market, Suite 1425  
Wichita, KS 67202

Lease Name Briggeman Well # 1  
County Pratt 142.45  
Well Total Depth 4383 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 910

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Bowers Drilling Inc. License Number 5435  
Address 125 North Market, Suite 1425, Wichita, KS 67202

Company to plug at: Hour: 3:20 p.m. Day: 29 Month: 10 Year: 19 87

Plugging proposal received from Bill Musgrove  
(company name) Bowers Drilling Inc. (phone) 316-262-6449

were: 5 1/2" at 4370' PBD 4220' Perfs at 3541-3964' (6sets)  
1st plug sand back to 3400' with 5 sx cement on top of sand through bailer,  
2nd plug pump 400 lbs. hulls and 100 sx light cement.

Plugging Proposal Received by Glenn Barlow & Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3:45 p.m. Day: 29 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3400' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 400 lbs. hulls and 100 sx light cement.  
Pumping pressure 50-150 psi and shut in 0 psi. Well on vacuum.

Checked plug on 10/30/87. Down 200'. Filled with 2 3/4 yds of Ready Mix.

Remarks: Used Thrifty Mix cement by B.J. Titan. Recovered 2000' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

(If you wish to observe this plugging.

DATE 11-9-87  
INV. NO. 1825B

Signed Dennis Rankin (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
11-5-87  
NOV 5 1987  
CONSERVATION DIVISION  
Wichita, Kansas