

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-20658-00-00  
Spot: CSWNWNE Sec/Twnshp/Rge: 5-27S-14W  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: STROBEL Well Number: 2  
County: PRATT Total Vertical Depth: 4625 feet

Operator License No.: 31142 Conductor Pipe: Size feet: 150.31  
Op Name: PETROLEUM PROPERTY SERVICES, INC Surface Casing: Size 12.75 feet: 275 WITH 415 SX CMT  
Address: 155 N. MARKET, STE 1010 Production: Size 5.5 feet: 4475 WITH 300 SX CMT  
WICHITA, KS 67202 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/09/2001 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3400' & 5 SX CMT. 1ST PLUG AT 930' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 100 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/09/2001 2:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4305'. PERFS AT 3484-90, 3940-44, 4045-50, 4063-67, 4126-30'. CIBP @ 4305'. PERFS AT 4332-36'. SANDED BACK TO 3361' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 930' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 100 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.


Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2030' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)  
NOV 13 2001  
INVOICED  
DATE 11-14-01  
INV. NO. 2002060941

RECEIVED  
11-14-2001  
NOV 14 2001  
KCC WICHITA

  
Form CP-2/3