

1041375

TO: STATE CORPORATION COMMISSION

API NUMBER ~~15-185-22,726~~ 15-151-20077-00-0
C SE NW SEC. 36, T 27 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 3410 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2195 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME GIBBONS WELL # 6

TECHNICIAN'S PLUGGING REPORT

12/10

COUNTY PRATT

142.61

OPERATOR LICENSE # 3911

WELL TOTAL DEPTH 4388 FEET

OPERATOR: RAMA OPERATING CO., INC. PRODUCTION CSG: SIZE 5 1/2" @ 4387' WITH 125 SX

NAME AND PO BOX 159 SURFACE CASING: SIZE 13 3/8" @ 180' WITH 350 SX

ADDRESS STAFFORD, KS 67578

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 10 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MONTE

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4324-28 & 4331-38

SANDED TO 4250' AND 5 SX CEMENT WITH DUMP BAILER. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 750' WITH 75 SX CEMENT. 2ND PLUG AT 210' WITH 75 SX CEMENT. 3RD PLUG AT 40' WITH 25 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 10 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT _____

SANDED TO 4250' AND 5 SX CEMENT WITH DUMP BAILER. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 750' WITH 75 SX CEMENT. 2ND PLUG AT 210' WITH 75 SX CEMENT. 3RD PLUG AT 40' WITH 25 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1999
12-22-99

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2409' OF 5 1/2" CASING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING DATE 12/22/99

INV. NO. 061028

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CP-2/3