

1070096

TO: STATE CORPORATION COMMISSION

5-28

API NUMBER 15-151-20,114-0000
C NE SE SEC. 35, T 27 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 1852 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 550 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME H. GIBBONS WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY PRATT 142.74

OPERATOR LICENSE # 3911

WELL TOTAL DEPTH 4392 FEET

OPERATOR: RAMA OPERATING CO, INC PRODUCTION CSG: SIZE 5 1/2" @ 4391' WITH 100 SX

NAME AND PO BOX 159 SURFACE CASING: SIZE 13 3/8" @ 200 WITH 150 SX

ADDRESS STAFFORD, KS 67578

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL E-26,761 D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 4:00 PM DAY: 28 MONTH: 05 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4355-4359

1ST PLUG SAND BACK TO 4180', DUMP 5 SX CEMENT WITH BAILER. 2ND PLUG PUMP 10 SX GEL, 70 SX CEMENT WITH 200# HULLS AT 720'. 3RD PLUG PUMP 70 SX CEMENT AT 240'. 4TH PLUG PUMP 15 SX CEMENT AT 30'.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 28 MONTH: 05 YEAR: 1999

ACTUAL PLUGGING REPORT _____

1ST PLUG SAND BACK TO 4180' DUMP 5 SX CEMENT WITH BAILER.

2ND PLUG PUMP 10 SX GEL, 70 SX CEMENT WITH 200# HULLS AT 720'.

3RD PLUG PUMP 70 SX CEMENT AT 240'.

4TH PLUG PUMP 15 SX CEMENT AT 30'. GOOD CIRCULATION.

23:21 80 JWW hhh

REMARKS: USED 60/40 POZ MIX, 6% GEL BY ALLIED. RECOVERED 2510' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

DATE 6-9-99 (DID) OBSERVE THIS PLUGGING. RC05-8-99

SIGNED [Signature]
(TECHNICIAN) FORM CP-2/3

INV. NO. 61018