

1 040795

10-25

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
2007 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,095-0000

C SE SE, SEC. 35, T 27 S, R 13 W XX

660 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Lease Name H. Gibbons Well # 1

Operator: RAMA Operating Co., Inc.

County Pratt

Name & Address P.O. Box 159

Well Total Depth 4385 142.51 feet

Stafford, KS 67578

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 13 3/8 feet 185

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 25 Month: 10 Year: 19 93

Plugging proposal received from David Brady

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4385' w/125 sx cement, Perfs at 4354-58'

1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 15 sx gel, 80 sx cement, 15 sx gel, 200 lbs. hulls, and 175  
sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 25 Month: 10 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 5 sx cement on top of sand  
bridge through bailer,

2nd plug pumped down 13 3/8" surface pipe with 300 lbs. hulls, 10 sx gel, 80 sx cement, 10 sx  
gel, 200 lbs. hulls and 175 sx cement.

Maximum pressure 200 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(old / ~~old~~) observe this plugging.

DATE 11-5-93

INV. NO. 39146

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
10-28-93  
OCT 20 1993  
CONSERVATION DIVISION  
Wichita, Kansas