

1040796

10-25

15-151-20136-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-15,957

C SE NE, SEC. 35, T 27 S, R 13 W, EX

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Operator: RAMA Operating Co., Inc.

Name:

Address P.O. Box 159

Stafford, KS 67578

Lease Name Lunt Well # SWD

County Pratt

Well Total Depth 4675 151.93 feet

Conductor Pipe: Size feet

Surface Casing: Size 13 3/8 feet 205

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling

License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 25 Month: 10 Year: 1993

Plugging proposal received from David Brady

(company name) Kelso Casing Pulling

(phone) 316-938-2943

were: 7" at 4472' w/100 sx cement, CIBP 4450', Open hole 4472-4675', casing parted @ 3520'

Junk in hole up to 3520', 8 3/4" hole from 205' to TD

1st plug sand back to 3520' and dump 7 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 15 sx gel, 80 sx cement, 15 sx gel, 200 lbs. hulls and 175 sx cement

Plugging Proposal Received by Richard Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 p.m. Day: 25 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3470' and dumped 7 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 13 3/8" surface pipe with 400 lbs. hulls, 15 sx gel, 80 sx cement, 15 sx gel, 200 lbs. hulls and 175 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 7" casing.

(If additional description is necessary, use BACK of this report)

I (did / observe) this plugging.

DATE 11-5-93

INV. NO. 39147

Signed

Stephen J. Pifer
(TECHNICIAN)

STATE CORPORATION COMMISSION
10-28-93
OCT 28 1993

CONSERVATION DIVISION
Wichita, Kansas