

25

1 030736

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,113-0000

SW NW SE, SEC. 2, T 27 S, R 13 WR
1650 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

Lease Name Sheegog Well # 1

Operator: Bowers Drilling Company, Inc.
Name &

County Bratt 143.00

Address 125 N. Market, Ste. 1425
Wichita, KS 67202

Well Total Depth 4400 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 423

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clark Corporation License Number 5105

Address 107 W. Fowler, Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: _____ Day: 6 Month: August Year: 19 86

Plugging proposal received from Bill Musgrove

(company name) Bowers Drilling Company, Inc. (phone) (316) 886-5520

were: 4 1/2" at 4394' PBDT at 3639' Perfs at 4299- , 3121-25'

1st plug sand back to 3075' and dump 4 sx cement on top of sand through bailer

2nd plug CIBP at 4250' and 3700'

3rd plug squeezed well with 3 sx hulls and 100 sx cement with 2 sx hulls mixed in

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:00 pm Day: 6 Month: August Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded bottom back to 3075' and dumped 4 sx cement on
top of sand through bailer, 2nd plug CIBP at 4250' and 3700', 3rd plug squeezed well
with 3 sx hulls and 100 sx cement with 2 sx hulls mixed in.

Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 65/35 Pozmix with 1% gel pumped by B. J. Titan.
Recovered 496' of 4 1/2" casing; 1820' - 1320' fell back in hole.
(If additional description is necessary, use BACK of this form.)

INVOICED
I () do not observe this plugging.

Signed Steve Durrant
(TECHNICIAN)

DATE AUG 12 1986 AUG 11 1986

INV. NO. 14707 RCD 8-11-86
8-6