

TO: 1070100  
STATE CORPORATION COMMISSION

7-21

API NUMBER 15-151-21,853  
NE NW NE SEC. 1, T 27 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CALBECK WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY PRATT

OPERATOR LICENSE # 9408

WELL TOTAL DEPTH 4370 142.09 FEET

OPERATOR: TRANS PACIFIC OIL CORPORATION PRODUCTION CSG: SIZE 5 1/2" @ 4369' WITH 175 SX

NAME AND 100 S MAIN, SUITE 200 SURFACE CASING: SIZE 10 1/2" @ 298' WITH 220 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 11:30 AM DAY: 21 MONTH: 07 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM BRIAN FRENZEL

(COMPANY NAME) DS&W (PHONE) 316-587-3361

WERE: PERFS AT 4317-23, 4084-86, 3900-08, 3865-69

SAND BACK TO 3800' WITH 5 SX CEMENT. PULL CASING. PLUG DOWN 10% 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 10% WIPER PLUG & 150 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 12:25 PM DAY: 21 MONTH: 07 YEAR: 1999

ACTUAL PLUGGING REPORT \_\_\_\_\_

SAND BACK TO 3800' AND 5 SX CEMENT.

PUMP DOWN 10% WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 10% PLUG - 150 SX CEMENT. MAXIMUM PRESSURE AT 300 PSIG. SHUT IN PRESSURE AT 200 PSIG.

RECEIVED  
7-26-99  
JUL 26 1999

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 5 1/2" CASING  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (PLD) OBSERVE THIS PLUGGING.

SIGNED [Signature]  
(TECHNICIAN) FORM CP-2/3

INVOICED

DATE 7-28-99

INV. NO. 60081

[Handwritten mark]

[Handwritten mark]