

1041362

TO: STATE CORPORATION COMMISSION

7-27

API NUMBER 15-097-20,102 ⁰⁰⁻⁰⁰
NE SW SE SW SEC. 25, T 27 S, R 19 W

CONSERVATION DIVISION - PLUGGING SECTION 510 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3450 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME DUNN WELL # 3

TECHNICIAN'S PLUGGING REPORT COUNTY KIOWA 35.00

OPERATOR LICENSE # 5118 WELL TOTAL DEPTH 647 FEET

OPERATOR: TGT PETROLEUM CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 640' WITH 100SX

NAME AND 7570 W 21ST BLDG. 1010-D SURFACE CASING: SIZE " @ ' WITH SX

ADDRESS WICHITA, KS 67205

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D-15,828 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR BASYE WELL SERVICING COMPANY LICENSE NUMBER 5670

ADDRESS PO BOX 149 STAFFORD, KS 67578-0149

COMPANY TO PLUG AT: HOUR: 11:30 AM DAY: 27 MONTH: 07 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM HAROLD BELLERIVE W/TGT PETROLEUM

(COMPANY NAME) BASYE WELL SERVICING COMPANY (PHONE) 316-234-5235

WERE: PERFS AT 533-35, 540-60. JUNK IN HOLE = 4 1/2" BAKER AD-1 TENSION PACKER AT 560'.

TAGGED PACKER WITH TUBING AND PICKED TUBING UP TO PLUG AT 550'.

CIRCULATED CEMENT INSIDE OF 4 1/2" CASING THROUGH 2 3/8" TUBING FROM 550' -0' WITH 50 SX CEMENT.

PULLED TUBING OUT OF HOLE. TOP OUT 4 1/2" CASING WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 27 MONTH: 07 YEAR: 1999

ACTUAL PLUGGING REPORT

TAGGED PACKER WITH TUBING AND PICKED TUBING UP TO PLUG AT 550'.

CIRCULATED CEMENT INSIDE OF 4 1/2" CASING THROUGH 2 3/8" TUBING FROM 550' TO 0' WITH 50 SX

CEMENT. PULLED TUBING OUT OF HOLE. TOP OUT 4 1/2" CASING WITH 10 SX CEMENT.

RECEIVED
8-5-99
AUG 5 1999

CONSERVATION DIVISION
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)
I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CH 2/3

INVOICED
DATE AUG 06 1999
INV. NO. 60123

[Handwritten signature]
[Handwritten circled number 2]