

To: 1 090669
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

4-17

Operator License / 3273

Operator: Herman Loeb

Name:

Address P.O. Box 524

Lawrenceville, IL 62439

15-097-00066-0000
API NUMBER 15- Drill completion date 3/6/62

C NW NW, SEC. 36, T 27 S, R 19 WAK

4620 feet from S section line

4620 feet from E section line

Lease Name Roy Einsel Well # 1

County Kiowa

Well Total Depth 4888 158.86 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11 a.m. Day: 17 Month: 4 Year: 19 96

Plugging proposal received from Roy Cox

(company name) Pratt Well Service (phone) 316-672-2531

work: 4 1/2" at 4874' w/175 sx cement, Perfs at 4284-86'

1st plug sand back to 4200' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 17 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls with 2 sx gel-hold in surface casing.

3rd plug ran tubing to 1250' and spotted 10 sx gel and 50 sx cement,

4th plug pulled to 370' and pumped 50 sx cement,

5th plug pulled to 30' and pumped 10 sx cement. Stayed full.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3424' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed [Signature] (TECHNICIAN)

INVOICED

DATE APR 23 1996

INV. NO. 45382

4-17

RECEIVED
KANSAS CORPORATION COMMISSION

4-19-96
APR 19 1996

CONSERVATION DIVISION
WICHITA, KS