

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20776-00-00  
Spot: CSENE Sec/Twnshp/Rge: 36-27S-19W  
1980 feet from N Section Line, 660 feet from E Section Line  
Lease/Unit Name: EINSEL F Well Number: 1  
County: KIOWA Total Vertical Depth: 4823 feet

Operator License No.: 5118 Conductor Pipe: Size feet:  
Op Name: TGT PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 710 WITH 500 SX CMT  
Address: 7570 W 21ST ST N, STE1010D PO BOX 75 Production: Size 4.5 feet: 4822 WITH 275 SX CMT  
WICHITA, KS 67275 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/05/2001 6:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: HAROLD BELLERIVE Company: TGT PETROLEUM Phone: (316) 773-2266

Proposed Plugging Method: SAND TO 4750' & 4 SX CMT. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 740' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE GEL FOR SPACER.

156.75

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/05/2001 7:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4818'. PERFS AT 4799-4803'. SANDED BACK TO 4400' & PUT 4 SX CMT ON TOP OF SAND BRIDGE. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG PUMP 8 SX GEL - 50 SX CMT - 2 SX GEL AT 1200'. 2ND PLUG AT 740' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED

DATE 3-30-01

INV. NO. 2001061562

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2600' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
Form CS-2  
MAR 22 2001  
3-22-2001  
CONSERVATION DIVISION  
WICHITA, Kansas

MAR 12 2001