

1030272

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,058-0000

C SW NW , SEC. 10 , T 27 S, R 19 W/X
3300 feet from N SE Corner of XXX section line
4620 feet from W SE Corner of XXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5118

Lease Name Kerr "A" Well # 1

Operator: TGT Petroleum Corp.

County Kiowa

Name & Address 209 E. William

Well Total Depth 4977 161.75 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 357

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 6:30 pm Day: 19 Month: September Year: 19 84

Plugging proposal received from Harvey Moore

(company name) Abercrombie Drilling (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1230' with 50 sx cement

2nd plug at 390' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Quaint
(TECHNICIAN)

Plug water well with 5 sx cement

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:00 pm Day: 19 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1230' with 50 sx cement, 2nd plug at 390' with 50 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate

mouse hole with 10 sx cement and plugged water well with 5 sx cement. STATE CORPORATION COMMISSION

SEP 24 1984

9-24-84
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

Signed Steve Quaint
(TECHNICIAN)

DATE 10-2-84

INV. NO. 3992