

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,999-0000

SE/4, Sec. 15, T 27 S, R 19 ~~W~~^W

660 feet from ~~N~~/S section line

660 feet from ~~W~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Logan "A" Well # 1

Operator: TXO Production Corp.
Name & 200 West Douglas, Suite 300
Address Wichita, KS 67202

County Kiowa

Well Total Depth 4925 feet 160.06

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor FWA Drilling Co., Inc. License Number 6165

Address P. O. Box 970, Yukon, OK 73099

Company to plug at: Hour: 8:45 pm Day: 17 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Mr. Hammond

(company name) FWA Drilling (phone) 316-265-9441

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1480' with 50 sx cement

2nd plug at 740' with 40 sx cement

3rd plug at 350' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement, 6th plug to circulate mousehole with 10 sx cement

Signed J. A. [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:00 pm Day: 17 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1480' with 50 sx cement, 2nd plug at 740' with

40 sx cement, 3rd plug at 350' with 40 sx cement 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate

rathole with 15 sx cement, 6th plug to circulate mousehole with 10 sx cement.

Remarks: Use 60/40 Pozmix 2% gel, 3% cc by Dowell

RECEIVED
STATE CORPORATION COMMISSION
2-29-84
FEB 29 1984

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

INVOICED

DATE 3-8-84

INV. No. 0626

2-17

Signed J. A. [Signature] ✓
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82