

1 010184

15-097-20353-0000

113 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A
C SW SW, SEC. 15, T 27 S, R 19 W/X
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Radar "A" Well # 1

Operator: Pickrell Drilling Company, Inc.
Name &
Address 100 North Market, Suite 205
Wichita, KS 67202

County: kiowa 155.68
Well Total Depth 4790 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 20 Month: 11 Year: 19 86

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4785' PBSD 4790' Openhole 4785-90' Elevation 2231' GL
1st plug 2 sx hulls and 25 sx cement and plug - stop plug at 4700',
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 70 sx cement, 10 sx gel, 1 sx hulls,
release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 20 Month: 11 Year: 1986

ACTUAL PLUGGING REPORT 1st plug pump 3 sx hulls, 25 sx common cement,
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 70 sx cement, 10 sx gel, 1 sx hulls,
released 8 5/8" wiper plug and pump 150 sx cement.

NOV 25 1986
RCD 11-25-86

Maximum pressure 700 psi and shut in 200 psi.

Remarks: Recovered 2400' of 4 1/2" casing. Used 60/40 Pozmix 6% gel and common cement by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-25-86 observe this plugging.

Signed Janet R. Smith
(TECHNICIAN)

DATE 11-25-86
INV. NO. 15431