

1070063

TO: 4-3 API NUMBER 15 - 097-20490-0000

STATE CORPORATION COMMISSION SE SW NE, SEC. 13 T 27 S, R 19 W

CONSERVATION DIVISION - PLUGGING SECTION 2970' FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650' FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME FARMER WELL # 1-13

TECHNICIAN'S PLUGGING REPORT COUNTY KIOWA 156.65

OPERATOR LICENSE # 30208 WELL TOTAL DEPTH 4820 FEET

OPERATOR: TRI-J TUBULARS, INC PRODUCTION CSG: SIZE 4 1/2" FEET 4802'

NAME AND 125 N. MARKET SUITE 1532 SURFACE CASING: SIZE 8 5/8" FEET 426'

ADDRESS WICHITA, KANSAS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR D S & W WELL SERVICING LICENSE NUMBER 6901

ADDRESS 403 W. FRONT, P.O. BOX 321, CLAFLIN, KS 67525-0231

COMPANY TO PLUG AT: HOUR: 10:30 DAY: 3 MONTH: 4 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KENT STRUBE

(COMPANY NAME) D S & W WELL SERVICING (PHONE) (316) 587-3361

WERE: PBTD 4760', PERFS 4555-4560,

1ST PLUG SAND BACK TO 4500' AND DUMP 4 SX CEMENT ON TOP OF SAND WITH BAILER

2ND PLUG PUMP 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8" WIPER PLUG, 125 SX CEMENT

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 11:45 DAY: 3 MONTH: 4 YEAR: 1998

ACTUAL PLUGGING REPORT 1ST PLUG SAND BACK TO 4500' AND DUMP 4 SX CEMENT ON TOP OF SAND WITH BAILER.

2ND PLUG PUMP 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8" WIPER PLUG, 125 SXS CEMENT

PUMPING PRESSURE 0-350 PSI - SHUT IN PRESSURE 100 PSI

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED, RECOVERED 2551' 4 1/2"
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED [Signature]
(TECHNICIAN) FORM CP-2/3

INVOICED

DATE 4-18-98

INV. NO. 50365

4-18

FAPR 0 19-98
4-8-98
Wichita, Kansas

[Signature]