

To: 1 060767
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 09700059-0001
C NW NW , SEC. 26, T 27 S, R 18 (W/B)
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061
Operator: Oil Producers, Inc. of Kansas
Name & Address 1346 North Woodlawn
Wichita, KS 67202

Lease Name Burkhardt Well # B-1
County Kiowa 159.41
Well Total Depth 4905 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 4635
Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 4:00 pm Day: 14 Month: January Year: 19 86

Plugging proposal received from Mike Gomez
(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4886' PBTD 4839' Perfs at 4797-99'; 4754-59'; 4745-50'
1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
and 100 sx cement.

 Plugging Proposal Received by Richard W. Lacey
 (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:00 pm Day: 14 Month: January Year: 19 86

ACTUAL PLUGGING REPORT Gel came up around the surface casing. Plugged through tubing with mud between plugs

1st plug sanded back to 4700' and dumped 4 sx cement on top of sand through bailer,
2nd plug at 1200' with 50 sx cement, 3rd plug at 600' with 40 sx cement, 4th plug at
350' with 40 sx cement, 5th & 6th plugs - solid bridge - hulls - plug at 40' --
to surface with 10 sx cement.

Remarks: Recovered 2100' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
1-16-86
JAN 16 1986
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED
(with ~~33333333~~) observe this plugging.
DATE 1-16-86
INV. NO. 12094

Signed Paul A. Luthie
(TECHNICIAN)