

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-01121-00-00
Spot: NWSEWSW Sec/Twnshp/Rge: 28-30S-16E
400 feet from S Section Line, 4345 feet from E Section Line
Lease Name: LONG Well #: 36V
County: WILSON Total Vertical Depth: 850 feet

Operator License No.: 3830
Op Name: A X & P, INC.
Address: PO BOX 1176
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	850		100 SX
SURF	7	44		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2015 8:00 AM
Plug Co. License No.: 33969 Plug Co. Name: HOUSEL, RICK DBA RICK'S WELL SERVICE
Proposal Rcvd. from: J J HANKE Company: A X & P, INC. Phone: (620) 325-5212

Proposed Plugging Method: Dry/Empty Hole.. RIH 1" pipe and circulate heavy gel to surface; place 10 sx cement on bottom. POH to @670'; place 10sx cement and POH to 250' and cement to surface.. Top off w. cement.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 06/30/2015 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was lowered to TD. 10 sacks of cement were then spotted. The cement string was pulled to 670 ft and 10 sacks of cement spotted. The cement string was pulled to 250 ft and the well pumped full. The cement string was removed and the well topped off with cement. A total of 51 sacks of portland cement were used to plug well - gel spacers between.

Perfs:

Top	Bot	Thru	Comments
798	801		
RECEIVED KCC DIST # 3 AUG 05 2015 CHANUTE, KS AD			

Remarks:

Plugged through: CSG

8/19/15 CKM

District: 03

Signed Alan Dunning
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
AUG 10 2015
CONSERVATION DIVISION
WICHITA, KS