

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-02021-00-01
Spot: NWNENE Sec/Twnshp/Rge: 7-16S-18W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: WERTH Well #: 1
County: RUSH Total Vertical Depth: 3620 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	8	3450		
L2	10	2560		
L3	12.5	1198		
PROD	6.625	3498		
SURF	15.5	493		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/04/2015 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2015 9:30 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

Perfs:

THIS WELL WAS REPLUGGED BECAUSE OF SALTWATER FLOWING TO THE SURFACE. IT WAS ORIGINALLY DRILLED & PLUGGED IN 1936. 3400' OF THE 8" LINER & 3200' OF THE 6 5/8" WAS RECOVERED IN 1936. IN 1936 THE BOTTOM PLUG WAS AT 3180'. 6/4/15: PUMP 50 SX COMMON CEMENT W/3% CC AT 1085'. PUMP 375 SX COMMON CEMENT WITH 3% CC AT 620'. 6/5/15: TAGGED AT 1070', 40' FILL, PUMP 300 SX COMMON CEMENT W/3% CC AT 620'. WAIT 2 HOURS TAG CMT AT 744'. PUMP 300 SX COMMON CMT W/3% CC AT 558'. WAIT 2 HOURS. TAG AT 600'. PUMP 225 SX COMMON CMT W/3% CC AT 558'. 6/8/15: TAGGED AT 140'. PUMP 115 SX 60/40 POZMIX 4% GEL . CIRCULATED TO SURFACE. TOP OFF. HOLE STAYING FULL.

Remarks: USED COMMON CEMENT W/3% CC & 60/40 POZMIX 4% GEL BY QUALITY. CONTROL NUMBER: 20150045001

Received
KANSAS CORPORATION COMMISSION
6-15-2015
JUN 15 2015
CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 01

RECEIVED
JUN 11 2015
KCC DODGE CITY

Signed _____

(TECHNICIAN)