

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-121-02608-0000
 Spot: SESENE Sec 36 Twp 16 S Rng 21 E / W
2849 Feet from N / S Line of Section
255 Feet from E / W Line of Section
 GPS: Lat: 38.615739 Long: 95.029209 Date: 10/2/14 8/8/13
 Lease Name: Tarr II Well #: 1-4 (T14)
 County: Miami Total Vertical Depth: 700 feet

Operator License No: 101
 Op Name: STATE OF KANSAS String DRIVE - Drive Pipe Size 10.000 Depth 15 Pulled 0 Comments EST.
 Address 1: 266 N. Main St. Ste. 220 T1 - Tubing I Size 2.000 Depth 700 Pulled 0 Comments EST.
 Address 2: _____
 City: WICHITA
 State: KS Zip Code: 67202 - 1513

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: E01521 Date/Time to Plug: 8/25/14 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 8/25/14 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
<p>CST... Dig out location and remove cement from over the old well that was cut off and buried. Remove the cement pad that was poured over the well. Install 12" pipe over the Drive Pipe and bring up above ground level. Run 1" inside 2" to 700 ft. Run 1" outside 2" to 300 ft. Try to wash inside 2" but 1" was plugged. Pull 1" out, remove plug and run back. Couldn't wash deeper. Wash outside 2" to 500 ft and hit hard. Start pumping cement inside 2". Couldn't get cement to proper weight. Try to pump cement outside 2", working to try to get cement heavier. CST kept telling me it would get there. Stayed between 11 and 13.5 lbs per gallon. I shut them down after 121 sacks of cement. Pull pipe out.</p> <p>KWS... Run 1" inside 2" to 125 ft. Run 1" outside 2" to 12 ft. Wash 1" to 150 ft inside and 75 ft outside 2". Pump Portland cement to surface. Pull pipe and top off well. Pump 21 sacks of cement. Well plugged. Pump total of 142 sacks of cement.</p>				

Remarks: Contract # 39389. Control # 20140052-002. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03
 RECEIVED
 KANSAS CORPORATION COMMISSION
 OCT 03 2014
 CONSERVATION DIVISION
 WICHITA, KS

 (Technician)
 Form: District Plugging Report - _____