

**Kansas Corporation Commission
District Plugging Report**

API Well Number: 15-121-02604-0000
 Spot: SESENE Sec 36 Twp 16 S Rng 21 E / W
2938 Feet from N / S Line of Section
155 Feet from E / W Line of Section
 GPS: Lat: 38.615979 Long: 95.028859 Date: 8/29/14 8/8/13
 (LS) Lease Name: Tarr II Well #: 1-6 (T-100)
 County: Miami Total Vertical Depth: 690 feet

Operator License No: 101 String Size Depth Pulled Comments
 Op Name: STATE OF KANSAS DRIVE - Drive Pipe 10.000 15 0 EST.
 Address 1: 266 N. Main St. Ste. 220 T1 - Tubing 1 2.000 690 0 EST.
 Address 2:
 City: WICHITA
 State: KS Zip Code: 67202 - 1513

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: E01521 Date/Time to Plug: 8/12/14 /
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed
 Plugging
 Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 8/12/14 / KCC Agent: Frank Guilfoyle

Actual Plugging Report:

Perfs:	Top	Bottom	Thru
Run 1" inside 2" with 1" tap to 600 ft. Pull out, remove tap and run 1" back to 625 ft. Run 1" outside 2" to 75 ft and hit. Wash 1" inside 2" to 690 ft. Wash 1" outside 2" to 445 ft and hit hard. Pump Portland cement from TD to surface inside and outside 2" to surface. Pull pipe and top off well. Pump total of 228 sacks of cement. Well plugged.			

Remarks: Contract # 39389. Control # 20140052-003. Regular section. GPS'ed by FG in NAD 83. Category II.
NAD83

Plugged Thru: TBG - Tubing Received **KANSAS CORPORATION COMMISSION** Plugged Due to Compliance Issue: Yes No

District: 03 SEP 04 2014
 CONSERVATION DIVISION WICHITA, KS Frank Guilfoyle
 (Technician)
 Form: District Plugging Report -