

**Kansas Corporation Commission**  
**District Plugging Report**

API Well Number: 15-121-02638-0000  
 Spot: NENWNE Sec 36 Twp 16 S Rng 21  E /  W  
4651 Feet from  N /  S Line of Section  
1508 Feet from  E /  W Line of Section  
 GPS: Lat: 38.620769 Long: 95.033599 Date: 12/21/14 8/8/13  
 Lease Name: L.S. Tarr II Well #: 10-6 (T-106)  
 County: Miami Total Vertical Depth: 675 feet

Operator License No: 101  
 Op Name: STATE OF KANSAS String DRIVE - Drive Pipe Size 10.000 Depth 15 Pulled 0 Comments EST.  
 Address 1: 266 N. Main St. Ste. 220 T1 - Tubing I Size 2.000 Depth 700 Pulled 0 Comments EST.  
 Address 2: \_\_\_\_\_  
 City: WICHITA  
 State: KS Zip Code: 67202 - 1513

Well Type: OG - Oil & Gas (-OIL) UIC Docket No.: \_\_\_\_\_ Date/Time to Plug: 10/22/14  
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.  
 Proposal Revd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 10/22/14 / \_\_\_\_\_ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Move equipment to location. Run 1" inside 2" to 125 ft and hit hard. Pull 1" out. Run 1" and tap to 125 ft and tried to screw into pipe. Nothing to screw into. Pick up pipe and drop several times and broke through. Run 1" to 500 ft. Pull out. Run 1" open inside 2" to 100 ft. Hit again. Run 1" outside 2" to 60 ft and hit gel. Pull 1" from inside and outside 2". Run 1" and reamer inside 2" to 500 ft. Pull out to perforate. Perforate 2". Run 1" inside 2" to 400 ft. Wash to 675 ft. Pump 27 bbls of cement and lost circulation. Pull 1" out and run outside of 2" to 60 ft. Pull out. On 10-22-14 wash 1" to 175 ft inside 2" and topped off. Wash 1" to 60 ft outside 2" and fill to surface. Pump total of 228 sacks of Portland cement. Well plugged.		<u>125</u>	<u>350</u>	<u>TBG - Tubing</u>

Remarks: Contract # 39389. Control # 20140052-005. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03  
**KCC WICHITA** Frank Guilfoyle  
 (Technician)  
 Form: District Plugging Report - \_\_\_\_\_  
**JAN 05 2015**  
**RECEIVED**