

API Well Number: 15-121-02642-0000  
 Spot: NENWNE Sec 36 Twp 16 S Rng 21  E /  W  
4811 Feet from  N /  S Line of Section  
1762 Feet from  E /  W Line of Section  
 GPS: Lat 38.621179 Long: 95.034489 Date: 12/2/14 8/8/13  
 Lease Name: Tarr Well #: 11-4 (T-114)  
 County: Miami Total Vertical Depth: 700 feet

**Kansas Corporation Commission**  
**District Plugging Report**

Operator License No: 101  
 Op Name: STATE OF KANSAS  
 Address 1: 226 N. Main St. St. 220  
 Address 2: \_\_\_\_\_  
 City: WICHITA  
 State: KS Zip Code: 67202 - \_\_\_\_\_

String	Size	Depth	Pulled	Comments
<u>DRIVE - Drive Pipe</u>	<u>11.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>700</u>	<u>0</u>	<u>EST.</u>
<u>PKR - Packer</u>	<u>1.000</u>	<u>460</u>	<u>460</u>	

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: E-01521 Date/Time to Plug: 10/24/14 / \_\_\_\_\_  
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.  
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed  
 Plugging  
 Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 10/24/14 / \_\_\_\_\_ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Run 1" outside 2" to 10 ft. Pull out. Run 1" inside 2" with reamer to 225 ft and hit. Pull 1" out. Remove reamer and put on 1" tap. Run back to 225 ft and screw into 1" and work loose. Pull out 1" and packer. Run 1" back to 460 and tried to screw into more pipe. Pull 1" out with nothing on tap. Run 1" and reamer to 460 ft. Pull out. Perforate 2". Wash 1" to 440 ft and hit hard. Pump Portland cement to surface. Pull 1" and top off well. Pump total of 26 sacks of cement. Well plugged.		<u>125</u>	<u>350</u>	<u>TBG - Tubing</u>

Remarks: Contract # 39389. Control # 20140052-007. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03 **KCC WICHITA** Frank Guilfoyle  
 (Technician)  
 Form: District Plugging Report - \_\_\_\_\_  
**JAN 05 2015**  
**RECEIVED**