

**Kansas Corporation Commission**  
**District Plugging Report**

API Well Number: 15-121-02644-0000  
 Spot: NENWNE Sec 36 Twp 16 S Rng 21  E /  W  
4915 Feet from  N /  S Line of Section  
1625 Feet from  E /  W Line of Section  
 GPS: Lat: 38.621459 Long: 95.034010 Date: 12/21/14 8/8/13  
 Lease Name: Tarr Well #: 11-6 (T-116)  
 County: Miami Total Vertical Depth: 700 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>DRIVE - Drive Pipe</u>	<u>10.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>226 N. Main St. St. 220</u>	<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>700</u>	<u>0</u>	<u>EST.</u>
Address 2: _____	<u>PKR - Packer</u>	<u>0.750</u>	<u>520</u>	<u>520</u>	
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - _____					

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: E-01521 Date/Time to Plug: 11/6/14 / \_\_\_\_\_  
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.  
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed  
Plugging  
Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 11/6/14 / \_\_\_\_\_ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Wash 1" through mud bridge at 10 ft inside 2". Hit pipe below mud. 3/4" pipe inside 2". Try to use tap . The 3/4" is very rotten. Fish out two pieces about 6" long. Then got out 2 pieces 4 to 6 ft long. Then recovered 550 ft of 3/4". Run 1" back to 550 ft inside 2" and hit stump of 3/4". Run 1" to 225 ft outside 2". Wash 1" to 550 ft outside 2". Pump Portland cement inside and outside 2" from 550 ft to surface. Pull pipe and top off well. Pump total of 221 sacks of cement. Well plugged.				

Remarks: Contract # 39389. Control # 20140052-008. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03 **KCC WICHITA** Frank Guilfoyle  
 (Technician)  
 Form: District Plugging Report - \_\_\_\_\_

JAN 05 2015  
RECEIVED