

API Well Number: 15-121-02645-0000

Kansas Corporation Commission

Spot: NENWNE Sec 36 Twp 16 S Rng 21 E / W
5040 Feet from N / S Line of Section
1837 Feet from E / W Line of Section
GPS: Lat: 38.621809 Long: 95.034749 Date: 12/2/14 8/8/13
Lease Name: Tarr II Well #: 12-6 (T-126)
County: Miami Total Vertical Depth: 675 feet

District Plugging Report

Operator License No: 101
Op Name: STATE OF KANSAS
Address 1: 266 N. Main St. Ste. 220
Address 2:
City: WICHITA
State: KS Zip Code: 67202 - 1513

String	Size	Depth	Pulled	Comments
<u>DRIVE - Drive Pipe</u>	<u>10.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>700</u>	<u>0</u>	<u>EST.</u>
<u>PKR - Packer</u>	<u>1.000</u>	<u>540</u>	<u>540</u>	

Well Type: OG - Oil & Gas (oil) UIC Docket No.: Date/Time to Plug: 10/20/14 /
Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
Proposal Revd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed
Plugging
Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
Date/Time Plugging Completed: 10/20/14 / KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Move equipment to location. Run 1" and tap, screw into 1" pipe. Work pipe and pull loose. Pull 10 joints of 1" out. Run 1" and tap back. Screw into 1" again. Work on it and got loose. Pull out 20 more joints of 1" with packer. Run 1" back to 540 ft inside 2". Run 1" to 200 ft outside 2" and hit mud. Wash 1" to 510 ft outside 2". Pump Portland cement to surface inside and outside 2". Pull pipe and top off well. Pump total of 210 sacks of cement. Well plugged.				

Remarks: Contract # 39389. Control # 20140052-010. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03

KCC WICHITA

JAN 05 2015

RECEIVED

Frank Guilfoyle
(Technician)

Form: District Plugging Report -