

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-121-02424-0000
 Spot: NWSENE Sec 36 Twp 16 S Rng 21 E / W
~~3716~~ 3714 Feet from N / S Line of Section
 1261 Feet from E / W Line of Section
 GPS: Lat: ~~38.01814993~~ 38.618149 Long: ~~-95.03272994~~ 95.032730 Date: ~~7/30/14~~ 8/8/13
 Lease Name: Tarr II Well #: 17-P (T17P)
 County: Miami Total Vertical Depth: 700 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>DRIVE - Drive Pipe</u>	<u>8.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>130 S. MARKET</u>	<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>700</u>	<u>0</u>	<u>EST.</u>
Address 2: _____	<u>T2 - Tubing 2</u>	<u>1.000</u>	<u>400</u>	<u>320</u>	<u>Packer left in 2"</u>
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - _____					

Well Type: OG - Oil & Gas - (Oil) UIC Docket No.: _____ Date/Time to Plug: 7/9/14 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 7/9/14 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Pull on 1" that might be on a packer. Pipe came loose and pulled out 320 ft of 1" pipe. Run 1" and overshot to 320 ft and could not get stubb sticking up. Run 1" and tap, but could not get pipe. Perforate well at 350 ft, 200 ft, and 75 ft. Run 1" to 320 ft inside 2". Run 1" to 400 ft outside 2". Wash to 420 outside 2" and hit hard. Pump Portland cement from TD to surface inside 2" and outside pipe. Pull pipe and top off well. Well plugged. Pump total of 111 sacks of Portland cement.		<u>75</u>	<u>350</u>	<u>TBG - Tubing</u>

RECEIVED
 KANSAS CORPORATION COMMISSION
 AUG 05 2014
 CONSERVATION DIVISION
 WICHITA, KS

Remarks: Contract # 39389. Control # 20140052-016. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 Frank Guilfoyle
 (Technician)
 Form: District Plugging Report - _____