

**Kansas Corporation Commission**  
**District Plugging Report**

API Well Number: 15-121-02611-0000  
 Spot: SESENE Sec 36 Twp 16 S Rng 21  E /  W  
3019 Feet from  N /  S Line of Section  
598 Feet from  E /  W Line of Section  
 GPS: Lat: 38.616220 Long: 95.030410 Date: 7/30/14 8/8/13  
 Lease Name: Tarr II Well #: 19 (T19)  
 County: Miami Total Vertical Depth: 515 feet

Operator License No: 101  
 Op Name: STATE OF KANSAS String DRIVE - Drive Pipe Size 10.000 Depth 15 Pulled 0 Comments EST.  
 Address 1: 130 S. MARKET  
 Address 2:  
 City: WICHITA  
 State: KS Zip Code: 67202 -

Well Type: OG - Oil & Gas (Oil) (D H) UIC Docket No.: Date/Time to Plug: 7/9/14 /  
 Plug Co License No.: 33749 (WAS OIL FIRST) (Pl Frank) Plug Co. Name: KEPLEY WELL SERVICE, LLC.  
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 7/9/14 / KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Run 1" and tap to 100 ft to try to fish out 1" pipe and swedge that CST lost in well. Could not get pipe. Pull out and run 2" overshot with swedge over lost 1". Pull out 2" and 1" that was lost. Run 1" to 350 ft and hit mud. Wash 1" to 515 ft. Pump Portland cement from TD to surface. Pull pipe and top off well. Pump total of 182 sacks of cement. Well plugged.				

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 AUG 05 2014  
 CONSERVATION DIVISION  
 WICHITA, KS

Remarks: Contract # 39389. Control # 20140052-017. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03  
Frank Guilfoyle  
 (Technician)  
 Form: District Plugging Report -