

**Kansas Corporation Commission**  
**District Plugging Report**

API Well Number: 15-121-02405-0000  
 Spot: SESENE Sec 36 Twp 16 S Rng 21  E /  W  
2848 Feet from  N /  S Line of Section  
590 Feet from  E /  W Line of Section  
 GPS: Lat: 38.615749 Long: 95.030379 Date: 10/2/14 8/8/13  
 Lease Name: Tarr II Well #: 2-2 (T22)  
 County: Miami Total Vertical Depth: 550 feet

Operator License No: 101  
 Op Name: STATE OF KANSAS  
 Address 1: 226 N. Main St. St. 220  
 Address 2: \_\_\_\_\_  
 City: WICHITA  
 State: KS Zip Code: 67202

String	Size	Depth	Pulled	Comments
<u>DRIVE - Drive Pipe</u>	<u>10.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
<u>TI - Tubing I</u>	<u>2.000</u>	<u>700</u>	<u>0</u>	<u>EST.</u>

Well Type: OG - Oil & Gas (oil) UIC Docket No.: \_\_\_\_\_ Date/Time to Plug: 8/25/14 / \_\_\_\_\_  
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.  
 Proposal Revd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed  
Plugging  
Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 8/25/14 / \_\_\_\_\_ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Run 1" inside 2" to 150 ft. Hit something. Pull 1" out and put on tap. Run 1" back with rubber fishing tool and hit something spongy. Twist pipe and got tight. Pull out with nothing. Run 1" back and worked to 415 ft and hit hard. Dig pit. Wash 1" outside from 12 ft to 15 ft and hit hard. Wash 1" inside 2" from 415 ft to 525 ft. Pull pipe. Perforate 2" three times. Run 1" to 525 ft and wash to 550 ft. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 35 sacks of cement. Well plugged.		<u>100</u>	<u>500</u>	<u>TBG - Tubing</u>

Remarks: Contract # 39389. Control # 20140052-018. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing RECEIVED KANSAS CORPORATION COMMISSION Plugged Due to Compliance Issue:  Yes  No

District: 03 OCT 03 2014 Frank Guilfoyle  
 CONSERVATION DIVISION WICHITA, KS (Technician)  
 Form: District Plugging Report - \_\_\_\_\_