

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-121-02610-0000
Spot: SWSENE Sec 36 Twp 16 S Rng 21 E / W
2995 Feet from N / S Line of Section
787 Feet from E / W Line of Section
GPS: Lat: 38.616159 Long: 95.031069 Date: 7/25/13 8/8/13
Lease Name: Tarr II Well #: 3-2 (T32)
County: Miami Total Vertical Depth: 725 feet

Operator License No: 101
Op Name: State of Kansas String DRIVE - Drive Pipe Size 8.500 Depth 20 Pulled 0 Comments EST.
Address 1: 130 S. Market T1 - Tubing 1 Size 2.000 Depth 725 Pulled 80 Comments EST.
Address 2: _____
City: Wichita
State: Ks Zip Code: 67202

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: E 01521.4 Date/Time to Plug: 5/6/14 5/20/14
Plug Co License No.: 34430 Plug Co. Name: CST Oil and Gas Corp
Proposal Rcvd from: Joe Taglieri Company Name: CST Oil and Gas Corp Phone: (720) 833-4203

Proposed Plugging Report:
Dig out location. Bring up to surface. Run/wash 1" to TD inside and outside 2" pipe. Pump Portland cement from TD to surface.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
Date/Time Plugging Completed: 5/20/14 / 1 KCC Agent: Frank Guilfoyle

Actual Plugging Report: 5/20/14

| Perfs: | Top | Bottom | Thru |
|---|-----|--------|------|
| Run 1" inside 2" to 690 ft. Run 1" outside 2" to 230 ft., Wash 1" down outside of 2" to 500 ft. Pump 21 sacks of Portland cement inside 2". Pump 138 sacks of Portland cement outside of 2". Kept trying to get cement to to proper weight. Too much trouble with equipment. Shut down. Let set for 2 days and washed 1" to 285 ft inside 2" and 85 ft outside 2". Pump Portland cement inside 2" to surface and outside 2" to surface. Pump first three batches into pit, (12 lbs per gallon, 11 lbs, 14 lbs) then 15.2 to 15.4 lbs until well filled to surface. Pumped 70 sacks of cement. Total of 229 sacks of Portland cement. | | | |

RECEIVED
KANSAS CORPORATION COMMISSION
7-2-2014
JUL 02 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: Contract # 39147. Control # 20140052-024. NAD 83 by FG. Reg Sect.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03
Frank Guilfoyle
(Technician)
Form: District Plugging Report - _____