

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-121-02617-0000
 Spot: NWSENE Sec 36 Twp 16 S Rng 21 E / W
3419 Feet from N / S Line of Section
1004 Feet from E / W Line of Section
 GPS: Lat: 38.617329 Long: 95.031829 Date: 2/23/15 8/8/13
 Lease Name: Tarr II Well #: 5-2 (T52)
 County: Miami Total Vertical Depth: 700 feet

Operator License No: 101
 Op Name: STATE OF KANSAS String DRIVE - Drive Pipe Size 10.000 Depth 15 Pulled 0 Comments EST.
 Address 1: 226 N. Main St. St. 220 String T1 - Tubing 1 Size 2.000 Depth 700 Pulled 0 Comments EST.
 Address 2: _____
 City: WICHITA
 State: KS Zip Code: 67202 - _____

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: E-01521 Date/Time to Plug: 1/21/15 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed
 Plugging
 Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 1/21/15 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Dig for and locate well. Remove cement pad, 2" came up with cement. Cut 2" loose from cement. Install surface to above ground. Fill in and level area. Run 1" inside 2" to 130 ft and hit. Run 1" outside 2" to 130 ft and hit also. Pull 1" from inside 2" and run tap back. Did not get anything. Run overshot and got nothing again. Run 1" back to 125 ft. Wash 1" inside to 610 ft. Wash 1" outside to 375 ft. Pump Portland cement to surface inside and outside 2". Pull pipe and top off well. Pump total of 166 sacks of Portland cement. Well plugged.	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____

Remarks: Contract # 39389. Control # 20140052-032. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No
 District: 03
 Received
 KANSAS CORPORATION COMMISSION
MAR 04 2015
 CONSERVATION DIVISION
 WICHITA, KS
 (Technician)
 Form: District Plugging Report - _____