

API Well Number: 15-121-02620-0000
 Spot: NWSENE Sec 36 Twp 16 S Rng 21 E / W
3533 Feet from N / S Line of Section
864 Feet from E / W Line of Section
 GPS: Lat: 38.617639 Long: 95.031339 Date: 8/20/14 8/8/13
 Lease Name: Tarr II Well #: 5-4 (T54)
 County: Miami Total Vertical Depth: 675 feet

Kansas Corporation Commission
District Plugging Report

(L.S.)

Operator License No: 101
 Op Name: STATE OF KANSAS String DRIVE - Drive Pipe Size 8100.000 Depth 15 Pulled 0 Comments EST.
 Address 1: 266 N. Main St. Ste. 220 String T1 - Tubing 1 Size 2.000 Depth 700 Pulled 0 Comments EST.
 Address 2: _____
 City: WICHITA
 State: KS Zip Code: 67202 - 1513

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: E01521 Date/Time to Plug: 7/31/14 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed
 Plugging
 Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 7/31/14 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Run 1" inside 2" to 675 ft. Run 1" outside 2" to 250 ft. Wash to 300 ft. Well unloads through 1" and plugs 1". Pull pipe, and unplug 1". Run 1" back and wash to 600 ft. Pump Portland cement from TD to surface inside and outside 2". Pull pipe and top off well. Pump total of 233 sacks of cement. Well plugged.	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____

Remarks: Contract # 39389. Control # 20140052-033. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03
 Received
 KANSAS CORPORATION COMMISSION
 SEP 04 2014
 CONSERVATION DIVISION
 WICHITA, KS

Frank Guilfoyle
 (Technician)
 Form: District Plugging Report - _____