

API Well Number: 15-121-02641-0000

Kansas Corporation Commission

District Plugging Report

Spot: NENWNE Sec 36 Twp 16 S Rng 21 E / W
4802 Feet from N / S Line of Section
1937 Feet from E / W Line of Section
GPS: Lat: 38.621160 Long: 95.035100 Date: 10/23/14 8/8/13
Lease Name: Tarr II Well #: 5-P (TSP)
County: Miami Total Vertical Depth: 700 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>DRIVE - Drive Pipe</u>	<u>8.000</u>	<u>15</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>266 N. Main St. Ste. 220</u>	<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>700</u>	<u>0</u>	<u>EST.</u>
Address 2:	<u>PKR - Packer</u>	<u>1.000</u>	<u>21</u>	<u>21</u>	
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - <u>1513</u>					

Well Type: OG - Oil & Gas (Oil) UIC Docket No.: _____ Date/Time to Plug: 9/26/14 / _____
Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
Date/Time Plugging Completed: 9/26/14 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report: _____ Perfs: _____ Top _____ Bottom _____ Thru _____

Dig out well and torch drive pipe and 2". Expose 1" inside of 2". Set surface, backfill and level area. Screw 1" and tap into 1". Work on getting 1" loose inside of 2". Put strain on 1" and let set. Pull 1" and packer out of 2". Run 1" inside of 2" to 600 ft. Run 1" outside 2" to 285 ft. Wash 1" down outside 2" to 625 ft. Wash inside to 600 ft. Pump Portland cement from TD to surface inside 2" and outside 2". Pull pipe and top off well. Pump total of 195 sacks of cement. Well plugged.

RECEIVED
KANSAS CORPORATION COMMISSION
11-5-2014
NOV 05 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: Contract # 39389. Control # 20140052-035. Regular section. GPS'ed by FG in NAD 83. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 Frank Guilfoyle
(Technician)
Form: District Plugging Report - _____