

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Crawford Drlg. & Exploration Inc.

Complete Address 217 N Water Wichita, Ks

Lease Name Dewayne Moore Well No. 2

Location NW/SE Sec. 35 Twp. 27 Rge. 13 (E) (W) W

County Pratt Total Depth 4384

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 10:30 AM Day 16 Month 7 Year 1971

The above well was plugged as follows:

196 ft 13 3/8 surface pipe cement circulated. 4380 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 4329 ft. Sand back to 4300 ft,
5 sacks cement with bailer. Pulled 3237 ft 5 1/2. Set 20 ft rock bridge
at 160 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. Russell Biberstein*
Well Plugging Supervisor

INVOICED

DATE 7-20-71
INV. NO. 4019-W