

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bowers Drlg. Co. Inc.

Complete Address 1434 Wichita Plaza Wichita, Ks

Lease Name Sheegog A Well No. 1

Location 0 N/2 S/2 SE Sec. 2 Twp. 27 Rge. 13 (E) W

County Pratt Total Depth 4380

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 3:00 PM Day 21 Month 9 Year 1970

The above well was plugged as follows:

451 ft of 8 5/8 surface pipe circulated. 4365 ft of 4 1/2 long string
cemented with 200 sacks. Top perf. 4041 ft. Sand back to 3975 ft,
4 sacks cement with bailer. Set 20 ft. rock bridge at 350 ft.
Fill hole with 5 yds redimix to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. Russell Biberstein
Well Plugging Supervisor

DATE 9/23/70
INV. NO. 2577-W