

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 45-26

LOCATION NW-NE-SE

SEC. 2 TWP 27 RGE. 26 13w

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Harwell

Operator Cross, Jocelyn - Varn Address 710 Schaefer Bldg Co
301 350 Pratt Kansas

Field _____ County Pratt

Total Depth 4389 Feet.

Plugging Contractor Forbes Casing Pulling Co

Plugging Contractor's License No. 49

Address Great Bend Kan

(Describe briefly the manner in which the well was plugged)

8 3/4" 349' Circulated With 250 sx Cement
5 1/2" 4350' Cemented With 150 sx
Plugged Back Halfway D.C. Plugs. 4020'-
4275'-4297'-4322' Top Perforations 3900' 3908'
hole filled With crushed rock to 3890' run
5 sx cement with check failed Pull 5 1/2"
Run 20 sx Gill Mud Plug and 100 sx Cement
through Plug Head on 8 3/4" Cement. 300' to face of
alar. Mud Plug - cement pumped
by Slope Cementing Co.

M. L. Rives
District Conservation Agent

Date 7-3-54

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 - 1954
7-6-54
CONSERVATION
Wichita

PLUGGING
FILE SEC 2 T 27 R 13w
BOOK PAGE 45 LINE 26