



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1974
6-12-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Terra Resources Inc

Complete Address Drawer C Great Bend, KS

Lease Name Calbeck A Well No. 1-1

Location SE/NE/NE Sec. 1 Twp. 27 Rge. 13 (E) (W) W

County Pratt Total Depth 4343

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kincaide Well Service Inc

Address Box 276 Ellinwood, KS License No. 727

Operation Completed: Hour 2:00 PM Day 8 Month 6 Year 1974

The above well was plugged as follows:
465 ft 8 5/8 surface cemented with 350 sacks. 4314 ft 5 1/2 long string
cemented with 175 sacks. Top perf. 4086 ft. Sand to 3702 ft, 5
sacks cement with bailer. Pulled 2150 ft 5 1/2. Pump 3 sacks hulls,
10 sacks gel, 125 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. Russell Bederstein
Well Plugging Supervisor

DATE 6/12/74

INV. NO. 9292-W